Bill of Quantity Items Print Preview

Current Tender Details

Tender ID	652714	**Enquiry/IFB/Tender Notice Number**	EE/TGEWIDC/RRD/NIT-48/2025-26, DT:24.11.2025
Name of Work	Construction of Rain Water Harvesting pits to 1- MPPS INJAPUR, 2- ZPHS BADANGPET, 3- ZPHS RAGANNAGUDA, 4- ZPHS PEDDA AMBERPET, 5- ZPHS JILLEL GUDA and 6- ZPHS BALAPUR in Ranga Reddy District. Under Ph-II of Package-1	**Tender Category**	Works
Tender Type	OPEN - NCB	**Estimated Contract Value**	511899
Bid Submission Closing Date	18/12/2025 02:00 PM	**Tender Evaluation Type**	Percentage

Back Print

BOQ Item Details

S.No	Subwork Name	Specification Number	Quantity	UOM	Rate(INR)	Amount(INR)
1	Work	As directed engineer-in-chief	30.00	Rmt	105.00	3150.00

Supplying and fixing of MS safety grill for rain water harvesting pit in open court yards using MS angles, flat, square bars including cost and conveyance of all materials, cutting, bending, welding, all operational charges, labour charges, overheads and contractor profit etc., complete for finished item of work.

	Subwork Name	Specification Number	Quantity	UOM	Rate(INR)	Amount(INR)
2	Work	1302 1319 & 1326	1.00	Rmt	103.70	104.00

Supplying and fixing of SWR/ PVC pipes (as per ISI standards) 4 Kg/Sq.cm. Prince/sudhakar or any ISI brand and fixing all special such as plain bends, off sets, door bends, single junctions, double junctions as per site requirement, fixing with PVC clamps if necessary with required number of Bombay nails including cost and conveyance of all materials to site, labour charges etc.complete for finished item of work at all floor levels. (APSS No. 1302 1319 & 1326) 75 mm dia

	Subwork Name	Specification Number	Quantity	UOM	Rate(INR)	Amount(INR)
3	Work	912.0	25.00	sqm	166.50	4163.00

Painting to New walls with two coats of Acrylic Emulsion paint of superior quality of approved brand and shade over base coat of cement primer interior grade -I making three coats in all to give an even shade after thoroughly brushing the surface to remove all loose powdered materials, including cost and conveyance of all materials, including cost and conveyance of all materials, cost of brushes, water to site, etc., sales & other taxes, all operational, incidental and labour charges such as scaffolding charges, lift charges, curing etc., complete for finished item of work in all floors for internal Walls.(APSS No. 912) in All Floors

	Subwork Name	Specification Number	Quantity	UOM	Rate(INR)	Amount(INR)
4	Work	As directed engineer-in-chief	0.90	cum	947.24	853.00

Supply and Filling of Coarse Sand

	Subwork Name	Specification Number	Quantity	UOM	Rate(INR)	Amount(INR)
5	Work	As directed engineer-in-chief	6.30	cum	1841.65	11602.00

Supply and Filling of 20mm metal

	Subwork Name	Specification Number	Quantity	UOM	Rate(INR)	Amount(INR)
6	Work	As directed engineer-in-chief	9.00	cum	1530.65	13776.00

Supply and Filling of 40mm metal

	Subwork Name	Specification Number	Quantity	UOM	Rate(INR)	Amount(INR)
7	Work	As directed engineer-in-chief	3.60	cum	1114.65	4013.00

Supply and Filling of 65mm metal

	Subwork Name	Specification Number	Quantity	UOM	Rate(INR)	Amount(INR)
8	Work	901,903&904	24.07	sqm	472.20	11366.00

Plastering 12mm thick in two coats with base coat of 8mm thick in CM (1:6) and top coat of 4mm thick in CM (1:4) dubara sponge finish including cost and conveyance of all materials like cement, sand, water etc., to site, sales & other taxes on all materials,all operational, incidental and labour charges such as mixing mortar, scaffolding charges, lift charges, including cutting of Grooves wherever necessary as directed by Engineer - in - charge, finishing, curing, etc., complete but excluding seigniorage charges for Even Surfaces of Wall for finished item of work. (APSS 901,903 & 904)

	Subwork Name	Specification Number	Quantity	UOM	Rate(INR)	Amount(INR)
9	Work	501 & 504	3.57	cum	6858.40	24484.00

Brick Masonry in superstructure with CM (1:8) prop: using Fly ASH Bricks of size 290x225x140mm with compressive of 50 Kgs / Sqcm from approved source including cost and conveyance of all materials like cement, sand, fly ash bricks, water etc., to site, including sales & other taxes on all materials, all operational, incidental and labour charges such as mixing cement mortar, constructing masonry, scaffolding charges, lift charges, curing, etc., complete but excluding seigniorage charges for finished item of work. (APSS No. 501 & 504).

	Subwork Name	Specification Number	Quantity	UOM	Rate(INR)	Amount(INR)
10	Work	402.0	0.10	cum	5402.70	540.00

Plain Cement Concrete corresponding to M7.5 grade as per IS 456 equivalent to (1:4:8) proportion nominal mix (cement: fine aggregate: Coarse aggregate) using , 40mm size Hard Blasted Granite (IS383, 1970) metal from approved quarry including cost and conveyance of all materials like cement, sand, coarse aggregate, water etc. to site, including sales & other taxes on all materials, all operational, incidental, and labour charges such as mixing, laying and ramming concrete in layers in position not exceeding 15cm, finishing top surface, curing concrete, etc., complete but excluding seigniorage charges, for finished item of work for Foundations (APSS No. 402)

	Subwork Name	Specification Number	Quantity	UOM	Rate(INR)	Amount(INR)
11	Work	308.0	29.05	cum	385.40	11196.00

ZPHS Balapur : Earth work excavation and depositing on bank (manual means) with initial lead of 10m and initial lift of 3m in Loamy & Clayey Soils like BC Soils, Red Earth & Ordinary Gravelly Soils

	Subwork Name	Specification Number	Quantity	UOM	Rate(INR)	Amount(INR)

(SS 20-B) including all operational incidental labour charges such as shoring, strutting, sheeting, planking and dewatering including cost of hire charges of T & P, labour charges etc., complete for finished item of work excluding seignerage charges and dewatering charges etc., complete for Foundation of Building.(APSS No. 308)

	Subwork Name	Specification Number	Quantity	UOM	Rate(INR)	Amount(INR)
12	Work	As directed engineer-in-chief	30.00	Rmt	105.00	3150.00

Supplying and fixing of MS safety grill for rain water harvesting pit in open court yards using MS angles, flat, square bars including cost and conveyance of all materials, cutting, bending, welding, all operational charges, labour charges, overheads and contractor profit etc., complete for finished item of work.

	Subwork Name	Specification Number	Quantity	UOM	Rate(INR)	Amount(INR)
13	Work	1302 1319 & 1326	1.00	Rmt	103.70	104.00

Supplying and fixing of SWR/ PVC pipes (as per ISI standards) 4 Kg/Sq.cm. Prince/sudhakar or any ISI brand and fixing all special such as plain bends, off sets, door bends, single junctions, double junctions as per site requirement, fixing with PVC clamps if necessary with required number of Bombay nails including cost and conveyance of all materials to site, labour charges etc.complete for finished item of work at all floor levels. (APSS No. 1302 1319 & 1326) 75 mm dia

	Subwork Name	Specification Number	Quantity	UOM	Rate(INR)	Amount(INR)
14	Work	912.0	25.00	sqm	166.50	4163.00

Painting to New walls with two coats of Acrylic Emulsion paint of superior quality of approved brand and shade over base coat of cement primer interior grade -I making three coats in all to give an even shade after thoroughly brushing the surface to remove all loose powdered materials, including cost and conveyance of all materials, including cost and conveyance of all materials, cost of brushes, water to site, etc., sales & other taxes, all operational, incidental and labour charges such as scaffolding charges, lift charges, curing etc., complete for finished item of work in all floors for internal Walls.(APSS No. 912) in All Floors

	Subwork Name	Specification Number	Quantity	UOM	Rate(INR)	Amount(INR)
15	Work	As directed engineer-in-chief	0.90	cum	947.24	853.00

Supply and Filling of Coarse Sand

	Subwork Name	Specification Number	Quantity	UOM	Rate(INR)	Amount(INR)
16	Work	As directed engineer-in-chief	6.30	cum	1841.65	11602.00

Supply and Filling of 20mm metal

	Subwork Name	Specification Number	Quantity	UOM	Rate(INR)	Amount(INR)
17	Work	As directed engineer-in-chief	9.00	cum	1530.65	13776.00

Supply and Filling of 40mm metal

	Subwork Name	Specification Number	Quantity	UOM	Rate(INR)	Amount(INR)
18	Work	As directed engineer-in-chief	3.60	cum	1114.65	4013.00

Supply and Filling of 65mm metal

	Subwork Name	Specification Number	Quantity	UOM	Rate(INR)	Amount(INR)
19	Work	901,903&904	24.07	sqm	472.20	11366.00

Plastering 12mm thick in two coats with base coat of 8mm thick in CM (1:6) and top coat of 4mm thick in CM (1:4) dubara sponge finish including cost and conveyance of all materials like cement, sand, water etc., to site, sales & other taxes on all materials,all operational, incidental and labour charges such as mixing mortar, scaffolding charges, lift charges, including cutting of Grooves wherever necessary as directed by Engineer - in - charge, finishing, curing, etc., complete but excluding seigniorage charges for Even Surfaces of Wall for finished item of work. (APSS 901,903 & 904)

	Subwork Name	Specification Number	Quantity	UOM	Rate(INR)	Amount(INR)
20	Work	501 & 504	3.57	cum	6858.40	24484.00

Brick Masonry in superstructure with CM (1:8) prop: using Fly ASH Bricks of size 290x225x140mm with compressive of 50 Kgs / Sqcm from approved source including cost and conveyance of all materials like cement, sand, fly ash bricks, water etc., to site, including sales & other taxes on all materials, all operational, incidental and labour charges such as mixing cement mortar, constructing masonry, scaffolding charges, lift charges, curing, etc., complete but excluding seigniorage charges for finished item of work. (APSS No. 501 & 504).

	Subwork Name	Specification Number	Quantity	UOM	Rate(INR)	Amount(INR)
21	Work	402.0	0.10	cum	5402.70	540.00

Plain Cement Concrete corresponding to M7.5 grade as per IS 456 equivalent to (1:4:8) proportion nominal mix (cement: fine aggregate: Coarse aggregate) using , 40mm size Hard Blasted Granite (IS383, 1970) metal from approved quarry including cost and conveyance of all materials like cement, sand, coarse aggregate, water etc. to site, including sales & other taxes on all materials, all operational, incidental, and labour charges such as mixing, laying and ramming concrete in layers in position not exceeding 15cm, finishing top surface, curing concrete, etc., complete but excluding seigniorage charges, for finished item of work for Foundations (APSS No. 402)

	Subwork Name	Specification Number	Quantity	UOM	Rate(INR)	Amount(INR)
22	Work	308.0	29.05	cum	385.40	11196.00

ZPHS Jillelguda : Earth work excavation and depositing on bank (manual means) with initial lead of 10m and initial lift of 3m in Loamy & Clayey Soils like BC Soils, Red Earth & Ordinary Gravelly Soils (SS 20-B) including all operational incidental labour charges such as shoring, strutting, sheeting, planking and dewatering including cost of hire charges of T & P, labour charges etc., complete for finished item of work excluding seignerage charges and dewatering charges etc., complete for Foundation of Building.(APSS No. 308)

	Subwork Name	Specification Number	Quantity	UOM	Rate(INR)	Amount(INR)
23	Work	As directed engineer-in-chief	40.00	Rmt	105.00	4200.00

Supplying and fixing of MS safety grill for rain water harvesting pit in open court yards using MS angles, flat, square bars including cost and conveyance of all materials, cutting, bending, welding,

	Subwork Name	Specification Number	Quantity	UOM	Rate(INR)	Amount(INR)

all operational charges, labour charges, overheads and contractor profit etc., complete for finished item of work.

	Subwork Name	Specification Number	Quantity	UOM	Rate(INR)	Amount(INR)
24	Work	1302 1319 & 1326	1.00	Rmt	103.70	104.00

Supplying and fixing of SWR/ PVC pipes (as per ISI standards) 4 Kg/Sq.cm. Prince/sudhakar or any ISI brand and fixing all special such as plain bends, off sets, door bends, single junctions, double junctions as per site requirement, fixing with PVC clamps if necessary with required number of Bombay nails including cost and conveyance of all materials to site, labour charges etc.complete for finished item of work at all floor levels. (APSS No. 1302 1319 & 1326) 75 mm dia

	Subwork Name	Specification Number	Quantity	UOM	Rate(INR)	Amount(INR)
25	Work	912.0	25.00	sqm	166.50	4163.00

Painting to New walls with two coats of Acrylic Emulsion paint of superior quality of approved brand and shade over base coat of cement primer interior grade -I making three coats in all to give an even shade after thoroughly brushing the surface to remove all loose powdered materials, including cost and conveyance of all materials, including cost and conveyance of all materials, cost of brushes, water to site, etc., sales & other taxes, all operational, incidental and labour charges such as scaffolding charges, lift charges, curing etc., complete for finished item of work in all floors for internal Walls.(APSS No. 912) in All Floors

	Subwork Name	Specification Number	Quantity	UOM	Rate(INR)	Amount(INR)
26	Work	As directed engineer-in-chief	0.90	cum	947.24	853.00

Supply and Filling of Coarse Sand

	Subwork Name	Specification Number	Quantity	UOM	Rate(INR)	Amount(INR)
27	Work	As directed engineer-in-chief	6.30	cum	1762.45	11103.00

Supply and Filling of 20mm metal

	Subwork Name	Specification Number	Quantity	UOM	Rate(INR)	Amount(INR)
28	Work	As directed engineer-in-chief	9.45	cum	1451.45	13716.00

Supply and Filling of 40mm metal

	Subwork Name	Specification Number	Quantity	UOM	Rate(INR)	Amount(INR)
29	Work	As directed engineer-in-chief	3.60	cum	1035.45	3728.00

Supply and Filling of 65mm metal

	Subwork Name	Specification Number	Quantity	UOM	Rate(INR)	Amount(INR)
30	Work	901,903&904	24.07	sqm	471.00	11337.00

Plastering 12mm thick in two coats with base coat of 8mm thick in CM (1:6) and top coat of 4mm thick in CM (1:4) dubara sponge finish including cost and conveyance of all materials like cement, sand, water etc., to site, sales & other taxes on all materials,all operational, incidental and labour charges such as mixing mortar, scaffolding charges, lift charges, including cutting of Grooves wherever necessary as directed by Engineer - in - charge, finishing, curing, etc., complete but

	Subwork Name	Specification Number	Quantity	UOM	Rate(INR)	Amount(INR)

excluding seigniorage charges for Even Surfaces of Wall for finished item of work. (APSS 901,903 & 904)

	Subwork Name	Specification Number	Quantity	UOM	Rate(INR)	Amount(INR)
31	Work	501 & 504	3.57	cum	6850.40	24456.00

Brick Masonry in superstructure with CM (1:8) prop: using Fly ASH Bricks of size 290x225x140mm with compressive of 50 Kgs / Sqcm from approved source including cost and conveyance of all materials like cement, sand, fly ash bricks, water etc., to site, including sales & other taxes on all materials, all operational, incidental and labour charges such as mixing cement mortar, constructing masonry, scaffolding charges, lift charges, curing, etc., complete but excluding seigniorage charges for finished item of work. (APSS No. 501 & 504).

	Subwork Name	Specification Number	Quantity	UOM	Rate(INR)	Amount(INR)
32	Work	402.0	0.10	cum	5295.80	530.00

Plain Cement Concrete corresponding to M7.5 grade as per IS 456 equivalent to (1:4:8) proportion nominal mix (cement: fine aggregate: Coarse aggregate) using , 40mm size Hard Blasted Granite (IS383, 1970) metal from approved quarry including cost and conveyance of all materials like cement, sand, coarse aggregate, water etc. to site, including sales & other taxes on all materials, all operational, incidental, and labour charges such as mixing, laying and ramming concrete in layers in position not exceeding 15cm, finishing top surface, curing concrete, etc., complete but excluding seigniorage charges, for finished item of work for Foundations (APSS No. 402)

	Subwork Name	Specification Number	Quantity	UOM	Rate(INR)	Amount(INR)
33	Work	308.0	29.05	cum	385.40	11196.00

ZPHS Pedda Amberpet : Earth work excavation and depositing on bank (manual means) with initial lead of 10m and initial lift of 3m in Loamy & Clayey Soils like BC Soils, Red Earth & Ordinary Gravelly Soils (SS 20-B) including all operational incidental labour charges such as shoring, strutting, sheeting, planking and dewatering including cost of hire charges of T & P, labour charges etc., complete for finished item of work excluding seignerage charges and dewatering charges etc., complete for Foundation of Building.(APSS No. 308)

	Subwork Name	Specification Number	Quantity	UOM	Rate(INR)	Amount(INR)
34	Work	As directed engineer-in-chief	40.00	Rmt	105.00	4200.00

Supplying and fixing of MS safety grill for rain water harvesting pit in open court yards using MS angles, flat, square bars including cost and conveyance of all materials, cutting, bending, welding, all operational charges, labour charges, overheads and contractor profit etc., complete for finished item of work.

	Subwork Name	Specification Number	Quantity	UOM	Rate(INR)	Amount(INR)
35	Work	1302 1319 & 1326	1.00	Rmt	103.70	104.00

Supplying and fixing of SWR/ PVC pipes (as per ISI standards) 4 Kg/Sq.cm. Prince/sudhakar or any ISI brand and fixing all special such as plain bends, off sets, door bends, single junctions, double junctions as per site requirement, fixing with PVC clamps if necessary with required number of Bombay nails including cost and conveyance of all materials to site, labour charges etc.complete for finished item of work at all floor levels. (APSS No. 1302 1319 & 1326) 75 mm dia

	Subwork Name	Specification Number	Quantity	UOM	Rate(INR)	Amount(INR)
36	Work	912.0	25.00	sqm	166.50	4163.00

Painting to New walls with two coats of Acrylic Emulsion paint of superior quality of approved brand and shade over base coat of cement primer interior grade -I making three coats in all to give an even shade after thoroughly brushing the surface to remove all loose powdered materials, including cost and conveyance of all materials, including cost and conveyance of all materials, cost of brushes, water to site, etc., sales & other taxes, all operational, incidental and labour charges such as scaffolding charges, lift charges, curing etc., complete for finished item of work in all floors for internal Walls.(APSS No. 912) in All Floors

	Subwork Name	Specification Number	Quantity	UOM	Rate(INR)	Amount(INR)
37	Work	As directed engineer-in-chief	0.90	cum	947.24	853.00

Supply and Filling of Coarse Sand

	Subwork Name	Specification Number	Quantity	UOM	Rate(INR)	Amount(INR)
38	Work	As directed engineer-in-chief	6.30	cum	1762.45	11103.00

Supply and Filling of 20mm metal

	Subwork Name	Specification Number	Quantity	UOM	Rate(INR)	Amount(INR)
39	Work	As directed engineer-in-chief	9.45	cum	1451.45	13716.00

Supply and Filling of 40mm metal

	Subwork Name	Specification Number	Quantity	UOM	Rate(INR)	Amount(INR)
40	Work	As directed engineer-in-chief	3.60	cum	1035.45	3728.00

Supply and Filling of 65mm metal

	Subwork Name	Specification Number	Quantity	UOM	Rate(INR)	Amount(INR)
41	Work	901,903&904	24.07	sqm	471.00	11337.00

Plastering 12mm thick in two coats with base coat of 8mm thick in CM (1:6) and top coat of 4mm thick in CM (1:4) dubara sponge finish including cost and conveyance of all materials like cement, sand, water etc., to site, sales & other taxes on all materials,all operational, incidental and labour charges such as mixing mortar, scaffolding charges, lift charges, including cutting of Grooves wherever necessary as directed by Engineer - in - charge, finishing, curing, etc., complete but excluding seigniorage charges for Even Surfaces of Wall for finished item of work. (APSS 901,903 & 904)

	Subwork Name	Specification Number	Quantity	UOM	Rate(INR)	Amount(INR)
42	Work	501 & 504	3.57	cum	6850.40	24456.00

Brick Masonry in superstructure with CM (1:8) prop: using Fly ASH Bricks of size 290x225x140mm with compressive of 50 Kgs / Sqcm from approved source including cost and conveyance of all materials like cement, sand, fly ash bricks, water etc., to site, including sales & other taxes on all materials, all operational, incidental and labour charges such as mixing cement mortar, constructing masonry, scaffolding charges, lift charges, curing, etc., complete but excluding seigniorage charges for finished item of work. (APSS No. 501 & 504).

	Subwork Name	Specification Number	Quantity	UOM	Rate(INR)	Amount(INR)
43	Work	402.0	0.10	cum	5295.80	530.00

Plain Cement Concrete corresponding to M7.5 grade as per IS 456 equivalent to (1:4:8) proportion nominal mix (cement: fine aggregate: Coarse aggregate) using , 40mm size Hard Blasted Granite (IS383, 1970) metal from approved quarry including cost and conveyance of all materials like cement, sand, coarse aggregate, water etc. to site, including sales & other taxes on all materials, all operational, incidental, and labour charges such as mixing, laying and ramming concrete in layers in position not exceeding 15cm, finishing top surface, curing concrete, etc., complete but excluding seigniorage charges, for finished item of work for Foundations (APSS No. 402)

	Subwork Name	Specification Number	Quantity	UOM	Rate(INR)	Amount(INR)
44	Work	308.0	29.05	cum	385.40	11196.00

ZPHS Ragannaguda: Earth work excavation and depositing on bank (manual means) with initial lead of 10m and initial lift of 3m in Loamy & Clayey Soils like BC Soils, Red Earth & Ordinary Gravelly Soils (SS 20-B) including all operational incidental labour charges such as shoring, strutting, sheeting, planking and dewatering including cost of hire charges of T & P, labour charges etc., complete for finished item of work excluding seignerage charges and dewatering charges etc., complete for Foundation of Building.(APSS No. 308)

	Subwork Name	Specification Number	Quantity	UOM	Rate(INR)	Amount(INR)
45	Work	As directed engineer-in-chief	30.00	Rmt	105.00	3150.00

Supplying and fixing of MS safety grill for rain water harvesting pit in open court yards using MS angles, flat, square bars including cost and conveyance of all materials, cutting, bending, welding, all operational charges, labour charges, overheads and contractor profit etc., complete for finished item of work.

	Subwork Name	Specification Number	Quantity	UOM	Rate(INR)	Amount(INR)
46	Work	1302 1319 & 1326	1.00	Rmt	103.70	104.00

Supplying and fixing of SWR/ PVC pipes (as per ISI standards) 4 Kg/Sq.cm. Prince/sudhakar or any ISI brand and fixing all special such as plain bends, off sets, door bends, single junctions, double junctions as per site requirement, fixing with PVC clamps if necessary with required number of Bombay nails including cost and conveyance of all materials to site, labour charges etc.complete for finished item of work at all floor levels. (APSS No. 1302 1319 & 1326) 75 mm dia

	Subwork Name	Specification Number	Quantity	UOM	Rate(INR)	Amount(INR)
47	Work	912.0	25.00	sqm	166.50	4163.00

Painting to New walls with two coats of Acrylic Emulsion paint of superior quality of approved brand and shade over base coat of cement primer interior grade -I making three coats in all to give an even shade after thoroughly brushing the surface to remove all loose powdered materials, including cost and conveyance of all materials, including cost and conveyance of all materials, cost of brushes, water to site, etc., sales & other taxes, all operational, incidental and labour charges such as scaffolding charges, lift charges, curing etc., complete for finished item of work in all floors for internal Walls.(APSS No. 912) in All Floors

	Subwork Name	Specification Number	Quantity	UOM	Rate(INR)	Amount(INR)
48	Work	As directed engineer-in-chief	0.90	cum	947.24	853.00

	Subwork Name	Specification Number	Quantity	UOM	Rate(INR)	Amount(INR)

Supply and Filling of Coarse Sand

	Subwork Name	Specification Number	Quantity	UOM	Rate(INR)	Amount(INR)
49	Work	As directed engineer-in-chief	6.30	cum	1841.65	11602.00

Supply and Filling of 20mm metal

	Subwork Name	Specification Number	Quantity	UOM	Rate(INR)	Amount(INR)
50	Work	As directed engineer-in-chief	9.00	cum	1530.65	13776.00

Supply and Filling of 40mm metal

	Subwork Name	Specification Number	Quantity	UOM	Rate(INR)	Amount(INR)
51	Work	As directed engineer-in-chief	3.60	cum	1114.65	4013.00

Supply and Filling of 65mm metal

	Subwork Name	Specification Number	Quantity	UOM	Rate(INR)	Amount(INR)
52	Work	901,903&904	24.07	sqm	472.20	11366.00

Plastering 12mm thick in two coats with base coat of 8mm thick in CM (1:6) and top coat of 4mm thick in CM (1:4) dubara sponge finish including cost and conveyance of all materials like cement, sand, water etc., to site, sales & other taxes on all materials,all operational, incidental and labour charges such as mixing mortar, scaffolding charges, lift charges, including cutting of Grooves wherever necessary as directed by Engineer - in - charge, finishing, curing, etc., complete but excluding seigniorage charges for Even Surfaces of Wall for finished item of work. (APSS 901,903 & 904)

	Subwork Name	Specification Number	Quantity	UOM	Rate(INR)	Amount(INR)
53	Work	501 & 504	3.57	cum	6858.40	24484.00

Brick Masonry in superstructure with CM (1:8) prop: using Fly ASH Bricks of size 290x225x140mm with compressive of 50 Kgs / Sqcm from approved source including cost and conveyance of all materials like cement, sand, fly ash bricks, water etc., to site, including sales & other taxes on all materials, all operational, incidental and labour charges such as mixing cement mortar, constructing masonry, scaffolding charges, lift charges, curing, etc., complete but excluding seigniorage charges for finished item of work. (APSS No. 501 & 504).

	Subwork Name	Specification Number	Quantity	UOM	Rate(INR)	Amount(INR)
54	Work	402.0	0.10	cum	5402.70	540.00

Plain Cement Concrete corresponding to M7.5 grade as per IS 456 equivalent to (1:4:8) proportion nominal mix (cement: fine aggregate: Coarse aggregate) using , 40mm size Hard Blasted Granite (IS383, 1970) metal from approved quarry including cost and conveyance of all materials like cement, sand, coarse aggregate, water etc. to site, including sales & other taxes on all materials, all operational, incidental, and labour charges such as mixing, laying and ramming concrete in layers in position not exceeding 15cm, finishing top surface, curing concrete, etc., complete but excluding seigniorage charges, for finished item of work for Foundations (APSS No. 402)

	Subwork Name	Specification Number	Quantity	UOM	Rate(INR)	Amount(INR)
55	Work	308.0	29.05	cum	385.40	11196.00

	Subwork Name	Specification Number	Quantity	UOM	Rate(INR)	Amount(INR)

ZPHS Badangepet: Earth work excavation and depositing on bank (manual means) with initial lead of 10m and initial lift of 3m in Loamy & Clayey Soils like BC Soils, Red Earth & Ordinary Gravelly Soils (SS 20-B) including all operational incidental labour charges such as shoring, strutting, sheeting, planking and dewatering including cost of hire charges of T & P, labour charges etc., complete for finished item of work excluding seignerage charges and dewatering charges etc., complete for Foundation of Building.(APSS No. 308)

	Subwork Name	Specification Number	Quantity	UOM	Rate(INR)	Amount(INR)
56	Work	As directed engineer-in-chief	40.00	Rmt	105.00	4200.00

Supplying and fixing of MS safety grill for rain water harvesting pit in open court yards using MS angles, flat, square bars including cost and conveyance of all materials, cutting, bending, welding, all operational charges, labour charges, overheads and contractor profit etc., complete for finished item of work.

	Subwork Name	Specification Number	Quantity	UOM	Rate(INR)	Amount(INR)
57	Work	1302 1319 & 1326	1.00	Rmt	103.70	104.00

Supplying and fixing of SWR/ PVC pipes (as per ISI standards) 4 Kg/Sq.cm. Prince/sudhakar or any ISI brand and fixing all special such as plain bends, off sets, door bends, single junctions, double junctions as per site requirement, fixing with PVC clamps if necessary with required number of Bombay nails including cost and conveyance of all materials to site, labour charges etc.complete for finished item of work at all floor levels. (APSS No. 1302 1319 & 1326) 75 mm dia

	Subwork Name	Specification Number	Quantity	UOM	Rate(INR)	Amount(INR)
58	Work	912.0	25.00	sqm	166.50	4163.00

Painting to New walls with two coats of Acrylic Emulsion paint of superior quality of approved brand and shade over base coat of cement primer interior grade -I making three coats in all to give an even shade after thoroughly brushing the surface to remove all loose powdered materials, including cost and conveyance of all materials, including cost and conveyance of all materials, cost of brushes, water to site, etc., sales & other taxes, all operational, incidental and labour charges such as scaffolding charges, lift charges, curing etc., complete for finished item of work in all floors for internal Walls.(APSS No. 912) in All Floors

	Subwork Name	Specification Number	Quantity	UOM	Rate(INR)	Amount(INR)
59	Work	As directed engineer-in-chief	0.90	cum	947.24	853.00

Supply and Filling of Coarse Sand

	Subwork Name	Specification Number	Quantity	UOM	Rate(INR)	Amount(INR)
60	Work	As directed engineer-in-chief	6.30	cum	1762.45	11103.00

Supply and Filling of 20mm metal

	Subwork Name	Specification Number	Quantity	UOM	Rate(INR)	Amount(INR)
61	Work	As directed engineer-in-chief	9.45	cum	1451.45	13716.00

Supply and Filling of 40mm metal

	Subwork Name	Specification Number	Quantity	UOM	Rate(INR)	Amount(INR)
62	Work	As directed engineer-in-chief	3.60	cum	1035.45	3728.00

Supply and Filling of 65mm metal

	Subwork Name	Specification Number	Quantity	UOM	Rate(INR)	Amount(INR)
63	Work	901,903&904	24.07	sqm	471.00	11337.00

Plastering 12mm thick in two coats with base coat of 8mm thick in CM (1:6) and top coat of 4mm thick in CM (1:4) dubara sponge finish including cost and conveyance of all materials like cement, sand, water etc., to site, sales & other taxes on all materials,all operational, incidental and labour charges such as mixing mortar, scaffolding charges, lift charges, including cutting of Grooves wherever necessary as directed by Engineer - in - charge, finishing, curing, etc., complete but excluding seigniorage charges for Even Surfaces of Wall for finished item of work. (APSS 901,903 & 904)

	Subwork Name	Specification Number	Quantity	UOM	Rate(INR)	Amount(INR)
64	Work	501 & 504	3.57	cum	6850.40	24456.00

Brick Masonry in superstructure with CM (1:8) prop: using Fly ASH Bricks of size 290x225x140mm with compressive of 50 Kgs / Sqcm from approved source including cost and conveyance of all materials like cement, sand, fly ash bricks, water etc., to site, including sales & other taxes on all materials, all operational, incidental and labour charges such as mixing cement mortar, constructing masonry, scaffolding charges, lift charges, curing, etc., complete but excluding seigniorage charges for finished item of work. (APSS No. 501 & 504).

	Subwork Name	Specification Number	Quantity	UOM	Rate(INR)	Amount(INR)
65	Work	402.0	0.10	cum	5295.80	530.00

Plain Cement Concrete corresponding to M7.5 grade as per IS 456 equivalent to (1:4:8) proportion nominal mix (cement: fine aggregate: Coarse aggregate) using , 40mm size Hard Blasted Granite (IS383, 1970) metal from approved quarry including cost and conveyance of all materials like cement, sand, coarse aggregate, water etc. to site, including sales & other taxes on all materials, all operational, incidental, and labour charges such as mixing, laying and ramming concrete in layers in position not exceeding 15cm, finishing top surface, curing concrete, etc., complete but excluding seigniorage charges, for finished item of work for Foundations (APSS No. 402)

	Subwork Name	Specification Number	Quantity	UOM	Rate(INR)	Amount(INR)
66	Work	308.0	29.05	cum	385.40	11196.00

MPPS Injapur: Earth work excavation and depositing on bank (manual means) with initial lead of 10m and initial lift of 3m in Loamy & Clayey Soils like BC Soils, Red Earth & Ordinary Gravelly Soils (SS 20-B) including all operational incidental labour charges such as shoring, strutting, sheeting, planking and dewatering including cost of hire charges of T & P, labour charges etc., complete for finished item of work excluding seignerage charges and dewatering charges etc., complete for Foundation of Building.(APSS No. 308)

Total(INR): 511899